

ACM Surveyed Locations At UAA Goose Lake Campus

This tabulation takes into account the most recent testing and remedial efforts. Some older detailed reports sometimes indicate the presence of ACM by screening methods, but more recent reports may show no regulated ACM in the same ACM areas. These contradictions are due to remedial efforts in ACM areas and more precise and accurate testing methods.

Data in red indicates known regulated ACM areas

| Building | Location | Description | PLM/PCM Screening Date | PLM/PCM Screening Results | TEM Definitive Date | TEM Definitive Results |
|---------------|--------------------------|---|------------------------|---------------------------|---------------------|------------------------|
| All locations | General survey | Ceiling Tiles | 01/08/97 | ND to trace | NA | NA |
| BMB | Mech Room | bulk sample | 06/11/86 | 11% - 17% | partially removed | 1987 |
| BMB | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| Bookstore | General survey | fireproofing | 06/11/86 | ND | NA | NA |
| CAS | Boiler Room | bulk sample | 06/11/86 | ND | NA | NA |
| CAS | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| CAS | Starbucks Vending | Remodel area | 12/15/06 | ND | NA | NA |
| SSB (CAS) | Mechanical | 1st & 3rd floor mech. And Room 205 | 06/05/07 | ND | NA | NA |
| CUDDY | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| ESB | Mech Room | bulk sample | 06/11/86 | 6% - 13% | partially removed | 1987 |
| ESB | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| GHB | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| GHB | Kiln area | Ceiling tiles | 02/21/97 | ND | NA | NA |
| GHB E&W | Mech Room | bulk sample | 06/11/86 | ND | NA | NA |
| GHB E&W | Mech Room | 4" valve | 06/11/86 | trace | NA | NA |
| GHBE | Men's Rm | Pipe chase | 11/07/96 | 5.0% | NA | NA |
| GHBW | Men's Rm | Pipe chase | 11/07/96 | 4.0% | NA | NA |
| J | Compressor Room | bulk sample | 06/11/86 | ND | NA | NA |
| J | General Survey | Ceiling tile mastic, brown | 11/07/96 | ND | NA | NA |
| J | Hazmat Survey | Fan housings & Covers | 05/05/05 | 40.0% | NA | NA |
| J | Hazmat Survey | Gray cement duct encasement | 05/05/05 | 25.0% | NA | NA |
| J | Hazmat Survey | Ceiling tile, drywall, fire proofing, glues | 05/05/05 | ND | NA | NA |
| J | Hazmat Survey | Floor tiles | 05/05/05 | 15.0% | NA | NA |
| K | Mech Rm West | Fireproofing | 08/23/96 | ND | NA | NA |
| K | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| K | Rm 234-A | attic room | 12/26/96 | ND | NA | NA |
| K | Mech. Room | by 1st floor return | 12/26/02 | ND | NA | NA |
| LIB | A Core | PCM Air analysis | 12/24/96 | trace | NA | NA |
| LIB | B Core | PCM Air analysis | 12/24/96 | trace | NA | NA |
| LIB | C Core | PCM Air analysis | 12/24/96 | trace | NA | NA |
| LIB | D Core | PCM Air analysis | 12/24/96 | trace | NA | NA |
| LIB | 1st floor attic | above circulation desk | 12/24/96 | ND | NA | NA |
| LIB | 1st floor attic | above reference desk | 12/24/96 | ND | NA | NA |
| LIB | A core west | HF Pipe insulation | 08/23/97 | 10.0% | NA | NA |
| SMB | Mech Room | bulk sample | 06/11/86 | 7% - 15% | partially removed | 1987 |
| SMB | General survey | Grey Fireproofing | 11/07/96 | ND | NA | NA |
| SMB | West Restroom | Hot water pipe chase | 08/21/00 | trace | NA | NA |
| SMB | All locations | 9x9 floor tiles | 08/21/00 | 1.1% | NA | NA |
| SMB | All locations | floor mastic | 08/21/00 | trace | NA | NA |
| SMB | West Restroom | gray cement/mortar | 08/21/00 | ND | NA | NA |
| SMB | West storage Rm | whit joint cpd | 08/21/00 | trace | NA | NA |
| SMB | West storage Rm | brown cove mastic | 08/21/00 | 1.1% | NA | NA |
| SMB | West storage Rm | wallboard | 08/21/00 | ND | NA | NA |
| SMB | West entry vestibule | black carpet mastic | 08/21/00 | trace | NA | NA |
| SMB | West entry vestibule | brown cove mastic | 08/21/00 | ND | NA | NA |
| SMB | West men's room | whit joint cpd | 08/21/00 | trace | NA | NA |
| SMB | West men's room | gray duct tape | 08/21/00 | ND | NA | NA |
| SMB | West men's room | white wall board | 08/21/00 | ND | NA | NA |
| SMB | West men's room | white joint cpd | 08/21/00 | 3.3% | removed | September 2000 |
| SMB | West Women's rooi | white joint cpd | 08/21/00 | 2.8% | removed | September 2000 |
| SMB | West men's room | tile grout | 08/21/00 | ND | NA | NA |
| SMB | West hallway ceiling | brown fiberboard | 08/21/00 | ND | NA | NA |
| SMB | West hallway | tan floor mastic | 08/21/00 | ND | NA | NA |
| SMB | East Restrooms | pipe chase | 08/21/00 | trace | NA | NA |
| SMB | Janitor closet | vinyl sheet | 08/21/00 | ND | NA | NA |
| SMB | Janitor closet | red sealant | 08/21/00 | ND | NA | NA |
| WWA | Mech Room | bulk sample | 06/11/86 | ND | NA | NA |
| WWA | Mech Room | fireproofing | 06/11/86 | trace | NA | NA |
| WWA | Boiler Rm | Fireproofing, white | 11/22/96 | 3.0% | NA | NA |
| WWA | General survey | Grey Fireproofing | 11/22/96 | ND | NA | NA |

ND = none detected

NA = not applicable

Trace = less than 1% (unregulated)

PLM = Polarized Light Microscopy

TEM = Transmission Electron Microscopy

PCM = Phase Contrast Microscopy